

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/08/15

CORNER DESIGNATION: The Northwest Corner of Section 15, Township 3 North, Range 31 East, J-13.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions, for cor to secs 9, 10, 15 & 16.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S9|S10
S16|S15
2015
PLS 54657

MONUMENT SET:

Re-established corner by double proportion measurement between one-quarter corners 1/2 mile North and South, the one-quarter corner between Sections 9 and 16 to the West and the Northeast corner of Section 15 to the East. At the re-established corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 20" below ground level, stamped as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet buried 20" in the ground, bears: grid azimuth 54°02', 23.7 feet.
A pink deep-1 magnet buried 20" in the ground, bears grid azimuth 137°54', 29.2 feet.
An blue deep-1 magnet buried 20" in the ground, bears grid azimuth 221°26', 23.7 feet.
A orange deep-1 magnet buried 20" in the ground, bears grid azimuth 324°21', 26.0'
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner located in a wheat field with no features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 762636.72
E = 8602109.95

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31J13



15-052-C

RENEWS: 6-30-16