

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/07/06

CORNER DESIGNATION: 3N31, N-17, The Northeast Corner of Section 22.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 14, 15, 22 & 23.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of the centerlines of Cresswell Road, (North-South) and Howdysshell Road extending East, as the best remaining evidence of original corner position.

**MONUMENT MARKING DETAIL:**

T3N R31E  
S15|S14  
S22|S23  
2006  
PLS 1106

**MONUMENT SET:**

At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with top cap 12" below gravel road surface. Monument marked as shown in monument marking detail.

From which:

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground level in UECA power pole No. 140001 bears North 13° East, 152.5 feet.

A blue Deep-1 magnet buried 24" below ground level bears South 30° East, 39.4 feet.

A purple Deep-1 magnet buried 24" below ground level bears South 35° West, 40.3 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" bears North 66° West, 13.6 feet. Attached witness post sign to road sign post 6" from rebar.

Attached bearing object sign to UECA power pole and iron rebar accessory. Buried bearing object signs with magnets.

LOCATION AND COMMENTS: Corner is located at the intersection of Cresswell and Howdysshell Rods.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757394.39  
E = 8607487.64

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31N17



*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*

*A6-462-C*