

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/17/06

CORNER DESIGNATION: 3N31, N-9, The Northwest Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. For corner to Secs. 17 & 18, 19 & 20.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S17|S16
S20|S21
2006
PLS 1106

MONUMENT SET:

Re-established corner position by holding the midpoint latitude between the intersection of the Easterly extended centerline of Peebler Road running West and a field and fence line extending South and the East one-quarter corner of Section 20. Held North-South field line for departure at the corner point. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

A silver Deep-1 magnet buried 24" below ground level bears North 48 1/2° East, 37.7 feet.
A blue Deep-1 magnet buried 24" below ground level bears South 35 1/2° East, 42.7 feet.
A purple Deep-1 magnet buried 24" below ground level bears South 47° West, 40.4 feet.
An orange Deep-1 magnet buried 24" below ground level bears North 40° West, 35.6 feet.
Set steel fence post with witness sign attached 1 foot North of monument. Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a North-South field line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 757336.58
E = 8596905.76

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31N9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08