

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/25/06

CORNER DESIGNATION: 3N31, R-5, The Southwest Corner of Section 20.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 19, 20, 29 & 30.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S19|S20
S30|S29
2006
PLS 1106

MONUMENT SET:

Reestablished corner position by record proportional departure between the re-established Southwest corner of Section 19 and Southeast corner of Section 20 and a point 17 feet South of East-West pole line for latitude, per power line easement reference. At reestablished corner position, set a 2 3/8 " brass cap on 1 1/4" x 30" galvanized iron pipe with cap 12" below ground level. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground level bears North 42° East, 41.5 feet.
 - A blue Deep-1 magnet buried 24" below ground level bears South 51 1/2° East, 34.0 feet.
 - A purple Deep-1 magnet buried 24" below ground level bears South 48° West, 33.3 feet.
 - A 3/4" brass washer stamped "PLS 1106", 1 foot above ground in UECA power pole No. 199001 bears North 75° West, 87.3 feet. Attached bearing object sign to the power pole.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located 3 feet South of the South edge of a gravel road, and 17 feet South of a power pole line, a crooked field line extends South from corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 751943.06
E = 8591718.46

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31R5



William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08