

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/25/06

CORNER DESIGNATION: 3N31, T-5, The West One-Quarter Corner of Section 29.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E

$\frac{1}{4}$

S30 | S29

2006

PLS 1106

MONUMENT SET:

Re-established corner position by single proportionate measure between the Northeast and Southeast corners of Section 30. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level. Monument marked as shown in monument marking detail.

From which:

A silver Deep-1 magnet buried 22" below ground level bears North 47 1/2° East, 35.2 feet

A blue Deep-1 magnet buried 22" below ground level bears South 39° East, 45.6 feet.

A purple Deep-1 magnet buried 22" below ground level bears South 54 1/2° West, 49.6 feet.

An orange Deep-1 magnet buried 22" below ground level bears North 51° West, 31.7 feet.

Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a poorly defined North-South field line in a actively farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 749300.99

E = 8591754.84


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31T5



William R. Wells



renews 6-30-08

176-462-C