

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/04/06

CORNER DESIGNATION: 3N31, V-13, The Northwest Corner of Section 34.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for corner to Secs. 27 & 28, 33 & 34.

MONUMENT AND ACCESSORIES FOUND: None. Held the intersection of the centerline of Barnhart Road North and South and a power pole and field line extending East as best remaining evidence of original corner position.

MONUMENT MARKING DETAIL:

T3N R31E
S28|S27
S33|S34
2006
PLS 1106

MONUMENT SET:

At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 10" below gravel road surface. Monument marked as shown in monument marking detail.

From which:

A 3/4" brass washer stamped "PLS 1106" 3 feet above ground level in UECA pole NO. 270000 bears South 89° East, 115.6 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked " OR PLS 1106 WA PLS 17372" bears South 21° West, 43.3 feet.

A 3/4" brass washer stamped "PLS 1106" 1' above ground level in UECA pole NO. 289000 bears North 84 1/2° East, 20.3 feet. Attached witness post sign to pole.

A 3/4" brass washer stamped "PLS 1106" 1' above ground level in a burned off power pole bears North 39 1/2° West, 36.8 feet.

Nailed bearing object signs to poles above brass washers.

LOCATION AND COMMENTS: Corner is located at the intersection of the centerline of Barnhart Road North and South and a power pole line extending East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 746713.51
E = 8602352.81

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/3N31V13

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08