

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/03/06

CORNER DESIGNATION: 3N31, Z-19, The South One-Quarter Corner of Section 35.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Josiah A. Burnett, under Contract No. 92, dated September 12, 1860. Record states: Set a post for 1/4 Sec. corner, drove charred stake and raised mound with trench, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N
R31E
1 S35
4 S2
T2N
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure on parallel of latitude between the reestablished Southwest and Southeast corners of section 35. At reestablished corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground level in a farmed field. Monument marked as shown in monument marking detail.

From which:

- A silver Deep-1 magnet buried 24" below ground level bears North 58° East, 40.5 feet.
 - A blue Deep-1 magnet buried 24" below ground level bears South 17 1/2° East, 33.8 feet.
 - A purple Deep-1 magnet buried 24" below ground level bears South 48 1/2° West, 43.1 feet.
 - An orange Deep-1 magnet buried 24" below ground level bears North 35° West, 35.1 feet.
- Buried bearing object signs with all magnets.

LOCATION AND COMMENTS: Corner is located in a farmed field. There are no definite features visible in the corner area.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 741445.18
E = 8610355.37

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

/3N31Z19

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08