

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/09/13

CORNER DESIGNATION: 3N32, A19, The North One-Quarter Corner of Section 2.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Thompson, under GLO Contract 106, dated August 1864, notes state: Set post for 1/4 Sec. corner in mound of Earth with charred stake, pits, trench &c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R32E
1 S35
4 S2
T3N
2013
PLS 54657

MONUMENT SET: Held the intersection of centerline of Midway Road and field berm to the North as best remaining evidence of the original corner position and set 2 3/8" brass cap on a 1 1/4" galvanized iron pipe, with top 10" below road surface, stamped as stated in "Monument Marking Detail", from which:

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears North 54 1/2 ° East, 37.2 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears South 57 ° East, 33.1 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears South 58 1/2 ° West, 39.6 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54756" bears North 33 1/2 ° West, 28.2 feet.

Attached bearing object signs to all accessories.

LOCATION AND COMMENTS:

In centerline of Midway Road at intersection with field berm to the North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 773751.59'

E= 8641829.49'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32A19



RENEWS: 6-30-14