

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/15/13

CORNER DESIGNATION: 3N32, C13, The West One-Quarter Corner of Section 3.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for 1/4 Sec. corner in mound of Earth with charred stake, pits, trench &c as per instructions. In Survey 88-18-B, by William Wells set a concrete nail at the intersection of centerline of Highway 37, between two old locust posts on field lines extending East and West, as evidence of the corner location.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

-30 FT W.C.
T3N R32E
1/4
S4|S3
2013
PLS 54657

MONUMENT SET: I reestablished the position determined on Survey No. 88-18-B from ties to said survey and held the position as the best evidence of the original corner position. The reestablished point falls in Highway 37 so a witness corner monument was set N 88°41'16" East, 30.00 feet from the corner point. At the witness corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, stamped as stated in "Monument Marking Detail", from which:
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657" in road bank bears North 03 1/2° West, 44.2 feet.
A 3/4" brass washer stamped "PLS 1106" in PP&L pole #030400 bears South 1/2° West, 72.0 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657" in road bank bears North 86 1/2° West, 48.9 feet.
A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657" in road bank bears South 38° West, 68.2 feet.
Attached bearing object tags to all accessories.

LOCATION AND COMMENTS:

Witness corner is 1 foot Easterly of old locust post.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 770829.04'
E= 8633939.88'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32C13



RENEWS: 6-30-14