

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/21/13

CORNER DESIGNATION: 3N32, C09, The West One-Quarter Corner of Section 4.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1/4
S5 | S4
2013
PLS 54657

MONUMENT SET: Held the intersection of field lines North-East and West as best remaining evidence of the original corner position and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level marked as shown in "Monument Marking Detail", from which:

A silver deep-1 magnet, buried 20" in the ground, bears North 42 1/2° East, 32.7 feet.
A pink deep-1 magnet, buried 20" in the ground, bears South 49° East, 35.7 feet.
A blue deep-1 magnet, buried 20" in the ground, bears South 36 1/2° West, 35.8 feet.
An orange deep-1 magnet, buried 20" in the ground, bears North 44° West, 27.8 feet.
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: At the point of intersection of field lines North, East and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 770755.01'
E= 8628648.81'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
3N32C09



RENEWS: 6-30-14