

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/17/13

CORNER DESIGNATION: 3N32, E01, The Northwest Corner of Section 7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract 100, dated August, 1, 1861. Notes state: Set charred stake with mound trench and pits as per instrs. for corner to to sections 1, 6, 7 & 12.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N
R31E R32E
1 | 6
12 | 7
2013
PLS 54657

MONUMENT SET: Held intersection of proportional latitude between the West 1/4 of Section 6 and Southwest corner of Section 18 with North-South field line as best available evidence of the original corner point. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground, marked as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet, buried 20" below ground, bears North 41 1/2° East, 37.1 feet.
 - A pink deep-1 magnet, buried 20" below ground, bears South 43 1/2° East, 40.1 feet.
 - A blue deep-1 magnet, buried 20" below ground, bears South 40° West, 41.8 feet.
 - An orange deep-1 magnet, buried 20" below ground, bears North 37 1/2° West, 27.9 feet.
- Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner falls in a North-South field line.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N= 767967.45'
E= 8617933.29'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East
Witnesses: Jason Wells, PLS
Dean Roy

Surveyor's Seal

\3N32E01

