

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/16/13

CORNER DESIGNATION: 3N32, E13, The Northwest Corner of Section 10.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for corner to Secs. 3, 4, 9 & 10 in mound of Earth with charred stake, pits, & as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL: Set railroad spike at corner point.

MONUMENT SET: Held the midpoint of a line between the East one-quarter corners of Sections 4 and 9 as the corner point. The point falls in the centerline of Highway 37 so it should be stated the visual centerline of Highway 37 was held for departure. At corner point in Highway 37, set a railroad spike below asphalt surface stamped "PLS 54657" +. From which:

A 3/4" brass washer stamped "PLS 1106" in PP&L pole #100902, bears South 89° East, 29.7 feet.

A 3/4" brass washer stamped "PLS 1106" in a Pacific Corp pole #01103032|100900, bears South 07° East, 247.0 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657" bears, South 18° West, 57.1 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657" bears, North 40° West, 23.2 feet.

Attached bearing object tags to all accessories.

LOCATION AND COMMENTS: Corner falls in centerline of Highway 37.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 768191.09'

E= 8633993.87'

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

\3N32E13



RENEWS: 6-30-14