

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 09/18/13

CORNER DESIGNATION: 3N32, E15, The North One-Quarter Corner of Section 10.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E  
1 S3  
4 S10  
2013  
PLS 54657

MONUMENT SET: Held the intersection with field lines North-South with a berm extending East as the best remaining evidence of the original corner location and monumented with a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with ground level, marked as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet, 20" in ground bears North 40° East, 26.8 feet.
  - A pink deep-1 magnet, 20" in ground bears South 50° East, 31.9 feet.
  - A blue deep-1 magnet, 20" in ground bears South 45° West, 21.8 feet.
  - An orange deep-1 magnet, 20" in ground bears North 37° West, 26.5 feet.
- Buried bearing object tags with magnets.  
Attached witness post sign to steel fence post 1.0 feet West of corner.

LOCATION AND COMMENTS: At intersection with field lines North-South and a berm East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 768274.60'  
E= 8636652.90'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

\3N32E15

