

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/22/13

CORNER DESIGNATION: 3N32, E05, The Northwest Corner of Section 8.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for corner to secs. 5, 6 7 & 8 in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
S6 | S5
S7 | S8
2013
PLS 54657

MONUMENT SET: Held a point 1 foot South of a 3 inch vertical field marker pipe with field berms extending East, West and South as best remaining evidence of the original corner position. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe flush with ground 1.0 feet South of 3" marker pipe with field berms East, West, and South. Cap marked as shown in "Monument Marking Detail" from which:

- A silver deep-1 magnet, buried 20" in ground, bears North 39° East, 34.1 feet.
 - A pink deep-1 magnet, buried 20" in ground, bears South 61° East, 33.7 feet.
 - A blue deep-1 magnet, buried 20" in ground, bears South 35 1/2° West, 35.7 feet.
 - An orange deep-1 magnet, buried 20" in ground, bears North 39° West, 27.1 feet.
- Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Corner is at intersection of field berms running East, West and South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 768006.53'
E= 8623454.83'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
3N32E05



RENEWS: 6-30-14