

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/14/13

CORNER DESIGNATION: 3N32, J11, The North One-Quarter Corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1 S9
4 S16
2013
PLS 54657

MONUMENT SET: Held the intersection of a line between the Northeast and Northwest corners of Section 16 with a North-South field berm as best remaining evidence of the original corner location. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground, marked as shown in "Monument Marking Detail", from which:
A silver deep-1 magnet, buried 20" below ground, bears North 55 1/2° East, 39.0 feet.
A pink deep-1 magnet, buried 20" below ground, bears South 50 1/2° East, 38.8 feet.
A blue deep-1 magnet, buried 20" below ground, bears South 41° West, 33.4 feet.
An orange deep-1 magnet, buried 20" below ground, bears North 50 1/2° West, 29.4 feet.
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Falls in a North-South field berm.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
Monument: N= 762876.80' Cor. position on latitudinal arc: N= 762876.63'
E= 8631453.80' E=8631453.81'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy
3N32J11



RENEWS: 6-30-14