

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/21/04

CORNER DESIGNATION: J-13, the Northeast Corner of Section 16, Township 3 North, Range 32 East, W.M., Umatilla County, Oregon.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by David P. Thompson, under GLO Contract No. 106, dated August 16, 1864. Record states: Set Stone 16x12x4 for corner to Secs. 9, 10, 15 & 16.

MONUMENT AND ACCESSORIES FOUND: State Highway No. 37 centerline and field line extending East.

MONUMENT MARKING DETAIL:



MONUMENT SET: Accepted centerline of State Highway No. 37 and field line extending East as best remaining evidence of original corner location. To avoid State Highway, set a witness corner monument, a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe buried 28" in the ground. Cap is marked as shown in the "Monument Marking Detail". Witness corner monument is located N 90°00'00" E a distance of 25.00 feet from true corner point.

New Accessories:

- A 3" diameter metal post set in ground bears East, 4.2 feet.
- A 3/4" brass washer stamped "PLS 1106", nailed 1 foot above ground level in PP&L pole #150900 bears S 39° E, 5.0 feet.
- A 5/8" x 24" rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" set flush with the ground bears S 49° W, 51.1 feet.
- A 5/8" x 24" rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" set flush with the ground bears N 64° W, 42.5 feet.
- Attached bearing object sign to power pole accessory.
- Set steel fence post 1 foot North of witness corner monument with "witness" sign attached.

LOCATION AND COMMENTS: Witness corner is located on East side of State Highway No. 37.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Marc Hammersla
3N32J13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04