

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 8/14/13

CORNER DESIGNATION: 3N32, J15, The North One-Quarter Corner of Section 15.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E

1 S10

4 S15

2013

PLS 54657

MONUMENT SET: Held a point in a North-South field line, 1 foot South of an old field marker post as best available evidence of the original corner location. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top flush with ground, marked as shown in "Monument Marking Detail", from which:

A silver deep-1 magnet, 20" below ground, bears North 49° East, 37.5 feet.

A pink deep-1 magnet, 20" below ground, bears South 59 1/2° East, 31.4 feet.

A blue deep-1 magnet, 20" below ground, bears South 40° West, 29.4 feet.

An orange deep-1 magnet, 20" below ground, bears North 54 1/2° West, 34.1 feet.

Attached witness post sign to 8" post by corner. Buried bearing object signs with magnets.

LOCATION AND COMMENTS: The field marker post fell over and was reset 2 feet South of monument.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 762964.37'

E= 8636760.25'

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

\3N32J15



RENEWS: 6-30-14