

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/27/13

CORNER DESIGNATION: 3N32, J07, The North One-Quarter Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1 S8
4 S17
2013
PLS 54657

MONUMENT SET: Held the intersection of a line between the Northeast and Northwest corners of Section 17 with the centerline of Westersund Road as the best remaining evidence of the original location and monumented the corner with a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 8" below ground, marked as shown in "Monument Marking Detail", from which:

A 5/8" x 24" rebar with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657", in road bank bears North 16 1/2° East, 47.6 feet.

A 5/8" x 24" rebar with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657", in road bank bears North 85° East, 13.9 feet.

A 5/8" x 24" rebar with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657", in road bank bears South 22° East, 40.0' feet.

A 5/8" x 24" rebar with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657", in road bank bears South 09 1/2° East, 82.1 feet.

Attached bearing object tags to all rebar.

LOCATION AND COMMENTS: Located in centerline of Westersund Road.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
Monument: N= 762788.68' Cor. position on latitudinal arc: N= 762788.51'
E= 8626151.60' E=8626151.60'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32J07

