

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/13/13

CORNER DESIGNATION: 3N32, L17, The West One-Quarter Corner of Section 14.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
1/4
S15 | S14
2013
PLS 54657

MONUMENT SET: Reestablished at held the intersection of field berms North, South and West as best remaining evidence of the original corner location and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with ground, marked as shown in "Monument Marking Detail", from which:

A silver deep-1 magnet buried 20" in the ground, bears North 49 1/2° East, 35.6 feet.

A pink deep-1 magnet buried 20" in the ground, bears South 46 1/2° East, 41.5 feet.

A blue deep-1 magnet buried 20" in the ground, bears South 54° West, 66.3 feet.

An orange deep-1 magnet buried 20" in the ground, bears North 61 1/2° West, 67.2 feet.

Buried bearing object tags with magnets and attached witness post sign to the railroad tie North of monument.

LOCATION AND COMMENTS: At the intersection with berms North, South and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 760393.11'
E= 8639458.14'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

\3N32L17



RENEWS: 6-30-14