

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 07/10/13

CORNER DESIGNATION: 3N32, N17, The Northwest Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract dated September 1864, notes state: Set post for corner to secs 14, 15, 22 & 23 in mound of earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E
S15|S14
S22|S23
2013
PLS 54657

MONUMENT SET: Held the intersection of Fulton Road East-West, with field lines extending North and South as best remaining evidence of the original corner position. At reestablished corner position, set a 2" aluminum cap on a 5/8" x 24" iron rod, 1" below asphalt surface stamped as stated in "Monument Marking Detail", from which:

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657" bears North 81° East, 107.6 feet.

Base of Umatilla County mile 1 sign bears South 58° East, 43.5 feet.

A 5/8" x 24" iron rod with a 1 1/4" purple plastic cap marked "Wells Surveying, PLS 54657" bears South 47° West, 29.6 feet.

A 3/4" brass washer stamped "PLS 1106", 1.0 feet above ground, on a PP&L pole #140001, bears North 70° West, 70.9 feet.

Attached bearing object tags to rebar and power pole. Attache witness pole sign to PP&L pole.

LOCATION AND COMMENTS:

At centerline of Fulton Road with fence and fenceline South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 757767.16'
E= 8639519.20'

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

\3N32N17



RENEWS: 6-30-14