

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla

DATE: 08-27-2012

CORNER DESIGNATION:

P-5, The West Quarter Corner of Section 20, Township 3 North, Range 32 East, Willamette Meridian, Umatilla County, Oregon.

PREVIOUS RENEWALS / SURVEYS, ETC.:

The corner was originally established by U.S. Deputy Surveyor, Daniel Chaplin, under contract No. 107 in 1864, who set a post for Sections 19 & 20 in a mound of Earth with charred stake, pits &c.

The survey for the establishment of Hagen Road (Road 179) in 1884 states "run North on line between Sections 19 & 20". No monument is mentioned or shown in the field survey notes for the corner in question.


An undated, hand prepared sketch found in the records of the Umatilla County Surveyors Office shows the hand written note "(charred stake). It appears that this sketch is from the old Hayes and Harris files.

An undated survey for George La Fontaine & Charles Hester prepared by Frank Hayes, Umatilla County Surveyor notes "Set 1" I.P."

MONUMENT AND ACCESSORIES FOUND:

Accepted the intersection of the apparent center line of Hagen Road and field lines running East and West as the best remaining evidence of the original corner position. See the 2012 J-U-B Engineers, Inc. Partition Plat for Tim Weidert for complete survey and corner details.

MONUMENT MARKING DETAIL:



MONUMENT SET:

Set 2-1/4" x 12" Aluminum pipe with a 3-1/4" Aluminum Cap with Deep-1 magnet in concrete, buried 6" below gravel road surface. The monument is approximately 0.5" East of the apparent center line of Hagen Road (12' gravel surface). The Aluminum Cap is marked as shown above in the Monument Marking Detail.

RECEIVED BY
Umatilla County Surveyor
Date: 9/10/12
Rec'd By: J. Des
No.: 12-125-R

NEW ACCESSORIES:

Set mag nail with red plastic washer stamped "JUB Control" in power pole, 1.0' above ground in West face of said power pole with bearing tag which bears S23°E, 43.62' from Aluminum Cap.

Set a 1/2" x 24" iron rebar with red plastic cap stamped "JUB Control" in the West shoulder of Hagen Road, 6" below road surface which bears S33°W, 12.60' from Aluminum Cap.

LOCATION AND COMMENTS:

The corner is located in Hagen Road.

REFERENCE OBJECT MEASUREMENT PROCEDURE:

Reference bearings were obtained with a Silva Ranger Compass with a declination of 15° East. Reference distances were measured using a 100-foot steel tape.


FIRM / AGENCY:

J-U-B Engineers, Inc.
2810 W. Clearwater Avenue, Suite 201
Kennewick, WA 99336
509-783-2144

WITNESSES:

Steven Day, Party Chief
Felipe Hernandez, Instrument Man

SURVEYOR'S SEAL



RECEIVED BY
 Umatilla County Surveyor
 Date: 9/10/12
 Rec'd By: S. Orw
 No.: 12-125-R