

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/15/13

CORNER DESIGNATION: 3N32, R21, The Southeast Corner of Section 23.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under GLO Contract 107, dated September 1864, notes state: Set post for corner to secs. 23, 24, 25 & 26, in mound of earth with charred stake, pits as per instructions. Corner evidence found on Survey No. 06-606-C, by Stephen Haddock, survey indicates acceptable corner evidence at the Intersection of County Road centerline and the possessory fence to the east.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R32E  
S23|S24  
S26|S25  
2013  
PLS 54657

MONUMENT SET: Held the intersection of the centerline of Campbell Road with a possessory fence line to the East as the best remaining evidence of the original corner position and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 12" below road surface level, stamped as shown in "Monument Marking Detail", from which:

A 3/4" brass washer stamped "PLS1106", above ground level in fence post bears South 84° East, 20.0 feet.

A 3/4" brass washer stamped "PLS 1106", above ground level in fence post bears South 14 1/2° East, 66.5 feet.

A 3/4" brass washer stamped "PLS 1106", above ground level in fence post bears North 52° West, 18.5 feet.

A 3/4" brass washer stamped "PLS 1106", above ground level in fence post bears North 20° West, 44.2 feet.

Nailed bearing object tags to wood fence posts by washers.

LOCATION AND COMMENTS: Located at the centerline of Campbell Road, with a fence and field line East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 752590.53'  
E= 8644903.85'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

\3N32R21

