

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/12/06

CORNER DESIGNATION: 3N31, T-25, The East One-Quarter Corner of Section 25.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated August 1, 1861. Record states: Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N
R31E R32E
1/4
S25 | S30
2006
PLS 1106

MONUMENT SET:

Re-established corner by single proportionate measure between the reestablished Northeast and Southeast corners of Section 25. At reestablished corner position, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe with cap 15" below ground surface. Monument marked as shown in monument marking detail.

From which:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106 WA PLS 17372" bears North 02 1/2° West, 16.3 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106 WA PLS 17372" bears South 03 1/2° West, 34.8 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106 WA PLS 17372" bears South 35° West, 67.4 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106 WA PLS 17372" bears South 69 1/2° West, 81.2 feet. Attached bearing object signs to all rebar accessories. Attached witness sign to steel fence post 3 feet West of monument.

LOCATION AND COMMENTS: Corner is located just North of a road bend in Stage Gulch Road. The centerline of the road extending West is 9 feet South of the monument. The centerline of the road extending South is nearly on line with the monument.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 749427.89
E = 8618175.27

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/3N31T25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08