

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 04/30/13

CORNER DESIGNATION: 3N32, V03, The North One-Quarter Corner of Section 31.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T3N R32E  
1 S30  
4 S31  
2013  
PLS 54657

MONUMENT SET: Reestablished corner position by single proportion measure between the Southwest and Southeast corners of Section 30. At the reestablished corner position, set 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 14" below ground in farmed field, marked as shown in "Monument Marking Detail", from which:  
A silver deep-1 magnet buried 20" in the ground bears North 51° East, 27.7 feet.  
A pink deep-1 magnet buried 20" in the ground bears South 46° East, 24.0 feet.  
A blue deep-1 magnet buried 20" in the ground bears South 41° West, 24.8 feet.  
An orange deep-1 magnet buried 20" in the ground bears North 44° West, 27.1 feet.  
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Located in small swale in a farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:  
Monument: N= 746847.09' Cor. position on latitudinal arc: N=746846.92'  
E= 8621249.67' E=8621249.68'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy  
3N32V03

