

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/30/13

CORNER DESIGNATION: 3N32, V07, The North One-Quarter Corner of Section 32.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by David Chaplin, under Contract 107, dated September 1864, notes state: Set post for 1/4 Sec. cor. in mound of Earth with charred stake pits & c as per instructions. Corner reestablished by John Kimbrell in 1906 in Record of Private Survey Book 1, Page 580. Kimbrell set a stone 12 x 8 x 5 inches. The City of Pendleton has acquired use of the Airport area and has made a number of surveys including Survey No. 89-123-B. It is believed the U.S. Army made surveys when the Pendleton Airbase was constructed, but no boundary survey information has ever been found.

MONUMENT AND ACCESSORIES FOUND: None.

## MONUMENT MARKING DETAIL:

T3N R32E  
1 S29  
4 S32  
2013  
PLS 54657

MONUMENT SET: Corner position was reestablished by single proportion measure between the Northeast and Northwest corners of Section 32. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 18" below ground in farmed field, marked as shown in "Monument Marking Detail", from which:

A silver deep-1 magnet buried 20" in the ground bears North 36 1/2° East, 32.2 feet.  
A purple deep-1 magnet buried 20" in the ground bears South 42° East, 32.3 feet.  
A blue deep-1 magnet buried 20" in the ground bears South 35° West, 30.5 feet.  
An orange deep-1 magnet buried 20" in the ground bears North 43° West, 33.2 feet.  
Buried bearing object tags with magnets.

LOCATION AND COMMENTS: Located 350 feet +/- South of East-West airport fence, 25 feet East of drainage swale running North-South. Old concrete head wall is located 150 feet +/- South of the corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:  
Monument: N= 746955.05' Cor. position on latitudinal arc: N= 746954.88'  
E= 8626544.02' E=8626544.02'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy  
3N32V07

