

OREGON CORNER RESTORATION FORM

Section: 22, 23 Township: 3N Range: 33E
County: Umatilla Date: 3/16/2012

Corner Designation: 3N33P17

Quarter corner common to Sections 22, 23, T3NR33E.

| | |
|-------|-----------------------|
| _____ | Condition Report Only |
| X | Not Found |
| X | Remonumented |
| _____ | Unrecorded |
| X | Surveyed In |
| X | Referenced Out |


Previous Renewals / Surveys, etc.

Originally surveyed by Chaplin in 1864. He set a 22" x 8" x 5" stone.
In 1882 Coffey reestablished the existing 22" x 8" x 5" stone in Private Survey No. 8, as recorded in Book 1, pg. 78.
In 1887 Currin and Noland found a 10" x 12" x 8" stone in a mound of earth with pits.

Monuments and Accessories Found: (Condition and Source):

None.

Diagram



Sketch

ORANGE
MAGNET

SILVER
MAGNET

BC

BLUE
MAGNET

PINK
MAGNET

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N755812.01
E8671264.99

Monument(s) Set (Procedures and Description):

A 1 1/8" x 30" galvanized iron pipe with 2 1/2" brass cap, stamped as shown above, 1.3' below the surface.
The corner location was reestablished by single proportionate method between neighboring corners to the North and South.

References Set:

- "Deep One" magnets by Berntsen.
- An orange magnet lies N 42° 50' W, 28.34', 1.7' deep.
- A silver magnet lies N 45° 15' E, 23.19', 1.8' deep.
- A pink magnet lies S 38° 15' E, 24.66', 1.7' deep.
- A blue magnet lies S 50° 10' W, 20.63', 1.8' deep.

Location and Comments:

The corner is located 1 1/2 miles South and 1/2 mile West of the intersection of Shafer Rd. and the Helix Highway. Sits near the breaks of Wildhorse Creek on a southeasterly facing slope. This area has been heavily farmed.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/13

RECEIVED BY:

Date: 7/10/2012
Rec'd By: S. Ores
No. 12-094-C

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055