

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 34E., W.M.

Corner Code No. N-17

Note: Monument marked as shown below


History of original corner establishment:

The most recent record of G.O. establishment indicates this corner was established by Currin and Noland, U.S. Deputy Surveyors, in 1887.

The record states:

Set post 4 ft. long, 4 ins. square in ground for cor to Secs. 14, 15, 22, 23. Dug pits 18 x 18 x 12 ins. in each Section 5 1/2 ft dist. Raised mound of earth 2 ft. high x 4 1/2 ft. base around post.

No record of surveys by C.E. Redfield, U.S. Indian Service Surveyor, were found in the Umatilla Agency records.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 4 way road intersection. After confirming the road intersection by survey, I re-establish the corner at the intersection of the 4 way road intersection. See Survey No. 92-26-B.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" G.I.P. 36" in ground at intersection of North-South, East-West dirt roads from which:

- A 5/8" by 30" rebar bears N 42 1/2°E - 33.26' dist. with a steel fence post 1 foot away with a Bearing Object sign attached.
- A 5/8" by 30" rebar bears S 59°E - 42.66' dist. with a steel fence post 1 foot away with a Bearing Object sign attached.
- A 5/8" by 30" rebar bears S 62°W - 36.71' dist. with a steel fence post 1 foot away with a Bearing Object sign attached.
- A 5/8" by 30" rebar bears N 1/2°W - 48.36' dist. in C/L of dirt road.

Each reference corner rebar is capped with a yellow plastic cap marked "W.R. Wells, PLS 1106".

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor

Date _____
Rec'd By *KP*
No. *92-26-B*