

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT
 Umatilla County Surveyor's Office

| | | |
|---|-------------|---|
| SECTION 16, 17, 20 and 21 | TOWNSHIP 3N | RANGE 36E |
| COUNTY: Umatilla | | DATE 6/20/08 |
| CORNER DESIGNATION: N-9 Corner common to sections 16, 17, 20, and 21 | | (Please check one) <input checked="" type="checkbox"/> Condition Report Only <input type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input type="checkbox"/> Surveyed In <input type="checkbox"/> Referenced Out |
| Previous Renewals / Surveys, etc. This corner was originally set by U.S. Deputy Surveyors J.P. Currin and J.E. Noland under their contract dated May 4, 1887. The deputy surveyors notes state, "set basalt stone 12x10x6 ins 8 ins in the ground for cor to Sections 16, 17, 20 and 21 and raised a mound of stone over it." In 1919 U.S. Indian Services Surveyor C.E. Redfield found the original monument and set an iron post in its place. | | |
| Monument(s) & Accessories Found: (Condition & Source) Found a 2" galvanized iron pipe with a 2 1/2" brass cap in a scattered mound of stone with a steel fence post 2 feet east of the mound. | | |
| Monument Detail: | Sketch: | |
| | | |
| Monument Set (Procedures and Description): | | |
| New Accessories: Rebuilt stone mound | | |
| Location & Comments: Corner is on a south slope 100 feet east of the head of a small draw on the east side of the finger ridge. | | Compass Declination: |
| Firm / Agency USKH Inc. Address: 5 N. Colville St. Walla Walla, WA 99362 Party Chief Damon Locke | | SURVEYOR'S SEAL |
| Notes | | |
| Witness | | |
| | | |

08-112-c

RENEWS 12/31/09
6/30/08