

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


R-21  
T3N R36E

CORNER TO SECTIONS 23, 24, 25 & 26, T3N, R36E

History of original corner establishment:

ESTABLISHED BY G.S. PERSHIN UNDER HIS CONTRACT No. 305, DATED SEPT. 20, 1878. HIS NOTES READ AS FOLLOWS:

SET STONE 12 x 10 x 8 ON STEEP EAST HILLSIDE FOR CORNER TO SEC. 23, 24, 25 AND 26, FROM WHICH:  
A FIR, 8 IN. DIAM. BR. S. 546° W. 68 LKS. DIST.  
A PINE, 20 IN. DIAM. BR. S. N 45° W, 148 LKS. DIST.  
NO OTHER TREES NEAR IN SEC. 24 & 25.



Description of corner evidence found:

FOUND OBT., 30" PINE, I OPENED AND FOUND SCRIBES "36 E S 23 B"  
BEARS N 45° W, 148 LKS. (= 97.7 FT.) GOOD CONDITION.

OTHER OBT IS MISSING.

Description of monument and accessories established to perpetuate the original location of this corner:

AT RECORD BEARING AND DISTANCE FROM FOUND OBT. I SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN, 12" IN GROUND, IN A LARGE MOUND OF STONE.


FROM WHICH MY NEW BT'S:

A 15" FIR, SCRIBED "T3N R36E S26 BT" BEARS S 38 1/4° W, 63.3 FT.

A 16" PINE, SCRIBED "T3N R36E S24 BT" BEARS N 11 3/4° E, 186.8 FT.

NO TREES WITHIN LIMITS IN SEC. 25.

T3N R36E  
S23 | S24  
S26 | S25  
1986  
LS 934



RECEIVED BY  
Umatilla County Surveyor  
Date 7-8-86  
Rec'd By EA  
No. 86-79-M  
Ref. 86-37-B

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)