

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N , R 37E. , W.M.

Corner Code No. Z-19

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878.

The original notes state:

Set spruce post on nearly level for 1/4 section corner from which:

A fir 12 in. dia. bears N 38°W, 30 links.
A fir 14 in. dia. bears S 30°W, 34 links.

In 1976, under Survey No. L-56-B, original evidence of the corner was recovered and the corner was re-monumented with a 2 1/2" brass cap on a 2" by 30" iron pipe.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" brass cap on a 2 1/2" galvanized iron pipe protruding 4" out of mound of stone. Corner located in North-South fence line about 10' North of fence corner with fences North and East from which:

Rotted remains of a 24" white fir bears S 30°W, 35.6' with parts of a chopped face remaining. (original bearing tree)
A 16" white fir bears S 06°E, 20.2' with scribes visible on a partly healed blaze. (RPE 2808 bearing tree).
A 12" white fir bears N 56°E, 21.7' with scribes visible on a partly healed blaze. (RPE 2808 bearing tree).

There is a steel fence post with an attention (54-4) sign attached, West of corner

Description of monument and accessories I established to perpetuate the original location of this corner:

Rebuilt earth and stone mound around corner monument.

Marked 2 new bearing trees:

A 10" white fir bears N 88°E, 10.6', scribed 1/4 S35 BT.
A 17" white fir bears S 17 1/2°W, 28.9', scribed 1/4 S2 BT.

All bearing trees have U.S.F.S. bearing tree tags or County bearing object signs attached.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

★ GPO—708-276

Umatilla County Surveyor

Date 9-91

Rec'd By KK

No. 91-55-C