


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-E 1/6 Cor. Sec. 2, T3N R37E

History of original corner establishment:

NO RECORD



C-20

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 26" IN GROUND, IN A MOUND OF STONE, FROM WHICH:

- A 9" FIR, SCRIBED "CE 1/6 S 2 BT" BEARS S 82 1/4° W, 5.8 FT.
- A 12" LARCH, SCRIBED "CE 1/6 S 2 BT" BEARS S 7 1/2° W, 10.3 FT.

SET A STEEL POST 3 FT. EAST OF CORNER WITH SIGN 54-4.

PAINTED A RED BAND AROUND BOTH BT'S AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED PROFESSIONAL LAND SURVEYOR

VICTOR M. MOLINE
OREGON JULY 27, 1990
VICTOR M. MOLINE
934

RECEIVED BY

Umatilla County Surveyor
Date 7-31-86
Rec'd By KA
No. 86-87-R

Office of SURVEYOR County of UMATILLA
State of OREGON, I hereby certify that the within instrument was filed in this office for record on the day of, 1986
(COUNTY OFFICIAL) by (DEPUTY)