

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**History of original corner establishment:**


Corner established by George S. Pershin under G.L.O. contract number 304 dated Sept., 19, 1878.

Surveyor General's records state:

Set a fir post on level for 1/4 sec cor from which:

A spruce 10" bears N 84° E., 49 lks dist marked 1/4 S BT (Later destroyed in subdivision of T 3 N R 38 E)

A fir 28" dia. bears S 60° W., 13 lks dist marked 1/4 S BT



**Description of corner evidence found:**

Found a fir stump 40" diam. with log lying alongside with full scribing visible (1/4 S BT) inside 6" overgrowth bears S 60° W., 8.58 ft. (13 lks) dist. with Forest Service location tag attached dated 6-1-64.

No trace of sec 6 BT.

**Description of monument and accessories established to perpetuate the original location of this corner**

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 6" above the ground with a 6' steel fence post 3' north with signs 54-4 and 54-2 attached.

new bearing tree:

A fir 12" diam. bears S 73° W., 61.5 ft. dist. marked 1/4 S 1 BT with a sign 54-3 attached 6" below a red band of paint and a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 26 day of August, 1976  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)