


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

D-20

S.E. 1/16 Cor. Sec. 2, T3N R37E

History of original corner establishment:

No Record



D-20

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, 26" IN GROUND, FROM WHICH:

A 15" FIR, SCRIBED "SE 1/16 S 2 BT" BEARS N 37 1/4° E, 11.5 FT.

A 19" FIR, SCRIBED "SE 1/16 S 2 BT" BEARS N 72 1/2° W, 5.4 FT.

SET A STEEL POST 3' SOUTH OF CORNER, WITH SIGN 54-4

PAINTED A RED BAND AROUND BOTH BT'S AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED PROFESSIONAL LAND SURVEYOR

Victor M. McKind

OREGON JULY 17, 1970 VICTOR M. McLIND 934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By KA

No. 86-88-B

Office of... SURVEYOR... County of... UMATILLA...

State of... OREGON... I hereby certify that the within instrument was filed in this office for record on the... day of... 19....

(COUNTY OFFICIAL) by (DEPUTY)