


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

S. 1/6 COR. TO SECTIONS 1 & 2, T3N R37E

History of original corner establishment:

No Record



D-21

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP, MARKED AS SHOWN ABOVE, IN A STONE MOUND, FROM WHICH:

A 10" FIR, SCRIBED "S 1/6 S 2 BT" BEARS N 32°W, 118.3 FT.

A 18" FIR, SCRIBED "S 1/6 S 2 BT" BEARS S 69°W, 133.7 FT.

SET A STEEL POST 2 FT. EAST OF CORNER, WITH SIGN 54-4.

PAINTED A RED BAND AROUND BOTH BT'S, AND ATTACHED SIGN 54-3 ABOVE BLAZE AND SIGN 54-4 TO BACK OF TREES.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Victor M. McLind*

OREGON JULY 17, 1970 VICTOR M. McLIND 934

RECEIVED BY

Umatilla County Surveyor

Date 7-31-86

Rec'd By KA

No. 86-89 R

Office of... SURVEYOR ... County of... UMATILLA ...

State of... OREGON ... I hereby certify that the within instrument was filed in this office for record on the... day of... , 19....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)