

USDA-FOREST SERVICE

Index

File No. D-25

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____


T 3N R. 37E

R.D. Walla Walla County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 2½" brass cap on a 2½" galv. iron pipe projecting 3" out of the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 16" western larch bears S 50° W, 51.75' with partly healed double blaze.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

7

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

8

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located about 800' south of a road running southwesterly. There is a wood post with location poster on the road.

3

Signature
Willie R. Wells

Title
PLS

Division

Headquarters
Pendleton, OR

Date
9/18/91

FS-7100-52 (3/66)

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Maintained existing corner monument by remounding it with earth. Set steel fence post South of corner and attached sign 54-2 and 54-9.

ACCESSORIES : DESCRIBE NEW BT^s WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Marked 1 new bearing tree:
A 15" western larch bears N 81 $\frac{1}{2}$ °W, 77.6' scribed S1/16 S1 BT.
New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze.
Attached signs 54-3 and 54-9 and painted face of blaze and a 6" red band around all bearing trees.

Work Done By W. R. Wells Title PLS Date 9/13/91 State Registration No. 1106
or Agency
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Surveyor Off. Date 12/31

REMARKS

Index File No. D-25 T. 3N R. 37E M. Will. Tract or Surv. No. Cor.
GPO: 1986 O-439-095

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 6" above the ground at base of south side of a 14" fir with a 6' steel fence post 3' south with sign 54-4 attached. Placed sign 54-2 on north and west side of 14" fir.

9

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A larch 13" diam. bears S 50° W., 51.75 ft. dist. marked S 1/16 S 1 BT with sign 54-3 attached 6" below a band of red paint and with a brass washer marked RPE 2808 nailed flush with BT blaze.

10

Work Done By James D. Hanley Title Engineer Date 7/28/76 State Registration No. ORPE 2808
or Agency

Certified Cor. Record Prepared? Yes Filed At: Pendleton, Oregon Date 8/ /76

11

REMARKS

12

13