


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by George S. Pershin under G.L.O. contract number 340 dated Sept., 26, 1879

Surveyor General's records state:

Set a basalt stone 16" x 14" x 4" on steep NE face of bluff for cor to secs 1-2-11 & 12 from which:



E-21

- A fir 10" diam. bears N 15° E., 70 lks. dist. marked T 3 N R 37 E S 1 BT
- A fir 12" diam. bears S 46° E., 24 lks. dist. marked T 3 N R 37 E S 12 BT
- A fir 11" diam. bears S 38° W., 15 lks. dist. marked T 3 N R 37 E S 11 BT
- A fir 16" diam. bears N 40° W., 34 lks. dist. marked T 3 N R 37 E S 2 BT

Description of corner evidence found:

A basalt stone 16" x 14" x 4" in place on NE face of steep hillside(65% slope)

- A 22" fir bears N 15° E., 46.2 ft.(70 lks) dist. with previously opened blaze with visible scribing S 1 inside 4" of overgrowth.
- A 34" fir bears S 46° E., 15.8 ft.(24 lks) dist. with healed blaze.
- A 28" fir bears S 38° W., 9.9 ft.(15 lks) dist. with healed blaze.
- A 30" fir bears N 40° W., 22.4 ft.(34 lks) dist. with healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2½" brass cap on a 2" iron pipe 31" long 6" above the ground in earth and rock mound with a 6' steel fence post 3' west with signs 54-4 and 54-2 attached.

Painted BT blazes with red paint and attached sign 54-3 to each BT.

Buried stone alongside brass cap monument.



Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.....
 by
 (COUNTY OFFICIAL) (DEPUTY)