


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-09
300400

History of original corner establishment:

1879, George S. Pershin, U.S. Deputy Surveyor, while surveying the Subdivisional lines of Fractional Township 3 North, Range 37 East, under G.L.O. Contract No. 340 established the corner as follows:
Set Basalt Stone 16 X 12 X 7 on N.W. face of spur for Cor. to Sec. 16, 17, 20 & 21
A Fir 24 ins. di. brs. N. 48° E. 166 lks dist
no other green trees near.



1900, William E. Campbell, U.S. Deputy Surveyor, while retracing the south boundary of sections 13, 14, 15, 16, 17 & 18 and completing the subdivisional lines of Fractional Township 3 North, Range 37 East, under G.L.O. Contract No. 718 described the corner as follows:
S. 89°45' W., on a blank line, S. bdy. of sec. 16 at 79.22 chs. intersect temp. closing cor. of secs. 21 and 21: and at 80.11 chs. intersect the cor. of secs. 16 and 17, which is a basalt stone 16 X 12 X 7 ins. on N.W. face of spur, marked and witnessed as described by the surveyor-general.

Description of corner evidence found:

Found on the northwest slope of a spur ridge a basalt stone 17" X 12" X 7", projecting 4" out of the ground, with 4 notches on the East edge and 3 notches on the Southerly end of the top edge, from which:

28" Douglas Fir Snag, bears N. 53° E., 106.3 feet (record N. 48° E. 166 links), with rotted out partially healed blaze (no scribing remains).

Description of monument and accessories established to perpetuate the original location of this corner:

I replace the stone with a 2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, set 25" in the ground, with a white SURV-KAP magnetic reference monument set in the bottom of the hole. Buried original stone on the North side of the aluminum monument. The cap is marked as shown, from which:



- 14" Douglas Fir, with a triple top, bears N. 67° E. 84.1 feet, scribed "T3N R37E S16" "BT".
- RM, 5/8" by 24" rebar with a 1 1/4" diameter yellow plastic cap stamped "UMATILLA N.F.", set 13" in the ground, bears N. 78°19' E., 36.39 feet.
- 6" Douglas Fir, bears S. 46 1/2° E., 14.3 feet, scribed "X" "BT".
- 9" Western Larch, bears N. 47 1/2° W., 33.3 feet, scribed "T3N R37E S17" "BT".

The bearing trees are double blazed and have a 3/4" diameter brass washer stamped "RLS 2308" nailed to the lower blaze between the "BT" scribing.

Work Performed By; David A. Schlaich (RLS 2308)
Witnessed By: Owen Bell
Equipment: Topcon GPT-6005C Total Station
Magnetic Declination: 17 1/2° East (1997 Bingham Springs Quad)
Date: October 23, 2002

REGISTERED PROFESSIONAL LAND SURVEYOR
David A. Schlaich
OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWAL DATE: 06/30/2004

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 20.....

..... by.....
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor:
Date 12-02
Rec'd By KK
No. 02-295-R