


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories I established to perpetuate the original location of this corner:

At a point on the Wilderness Boundary line and on the East-West centerline of Section 36, 492.86 feet West of the E 1/4 corner, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 24 inches in the ground, from which:

New Bearing Trees:

- A 21 inch diameter Ponderosa Pine bears S81°E, 32.88 feet marked WB 928 BT
- A 24 inch diameter Douglas Fir bears N60°W, 4.07 feet marked WB 928 BT

Raised a mound of stone around monument, 3 ft. base to top of cap.

Attached Bearing Tree and Land Survey Monument signs to the bearing trees.

Set a steel fencepost approximately 5 feet Northeasterly with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on Sept. 10, 1992.

Witnesses: Jeff Petersen and Jim Bennett



REGISTERED PROFESSIONAL LAND SURVEYOR

*[Signature]*  
 OREGON  
 JULY 10 1964  
 DUANE J. GRIFFITH  
 644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....

State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-92

Rec'd By RF

No. 92-118-R

\*GPO-591-971, 1988

WB 928