


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by George S. Pershin under GLO contract number 304, dated September 19, 1878. Surveyor General record states:

Set stone 16x12x4 on West hillside for corner to sections 25, 36, 30 and 31 from which:
 Fir 10 in diam brs N20°E, 26 lks dist
 Fir 8 in diam brs S18°E, 17 lks dist
 Fir 12 in diam brs S82°W, 10 lks dist
 Fir 10 in diam brs N42°W, 23 lks dist



Corner found by William E. Campbell under GLO contract number 718, dated May 1, 1900. Surveyor General record states:

A stone 16x12x4 ins marked and witnessed as described by the Surveyor General except that the marks on the NE and SE witness trees have been obliterated. Likewise the SW witness tree, a dead badly damaged fir has been defaced and a fir 12 ins diam bearing S46°W, 36 lks dist mkd T3N R37E S36 BT No tree in limit NW.

No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a stone 16x12x6 inches with no marks evident in a mound of stone.

Found a 14 inch diameter Douglas Fir snag N20°E, 10.9 feet with scribes visible.

Found no evidence of the other original accessories.

Description of monument and accessories I established to perpetuate the

original location of this corner: In place of found stone, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 26 inches in the ground, from which:

New Bearing Trees:

A 14 inch diameter Douglas Fir bears N66°E, 43.61 feet marked X BT
 A 24 inch diameter Ponderosa Pine bears S69°E, 34.43 feet marked T3N R38E S31 BT
 A 12 inch diameter Douglas Fir bears S61°W, 13.84 feet marked T3N R37E S36 BT
 A 14 inch diameter Douglas Fir bears N64°W, 28.70 feet marked T3N R37E S25 BT

Buried the unmarked stone South and alongside of monument.

Attached Bearing Tree and Land Survey Monument signs to the bearing trees.

Raised small mound of stone around monument.

Set a steel fencepost approximately 5 feet

North with Land Survey Monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 1, 1991.

Witnesses: Jeff Petersen and Jim Bennett



**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Duane I. Griffith
 OREGON
 JULY 10, 1964
DUANE I. GRIFFITH
 644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-92
 Rec'd By KF
 No. 92-118-R