


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-1

History of original corner establishment:

Corner Monumented by William E Campbell, under contract No.918, in 1900, set Stone, 15"X10"X4", 10" in the ground, marked 1/4 on East face. 32" diam. Fir, N.80°E., 15 links, marked 1/4S31BT Note: No restoration appears in county records



Description of corner evidence found:

Dead and down B.T. with scribe visible

REGISTERED PROFESSIONAL LAND SURVEYOR

Clayton J. Martin OREGON JULY 18, 1960 CLAYTON-JESSE MARTIN 1910

Description of monument and accessories | established to perpetuate the original location of this corner:

C.J. MARTIN SURVEYING 2751 JUNIPER ST. SWEET HOME, OR 97301

Set a 2 1/2" diam. brass cap in a 2"x30" iron pipe at record bearing and distance from B.T.

Cap Stamped T3N R36E R37E 1/4S31 RPLS 1910 1982

6" D.B.H. White Fir, S.88°E., 41.2', scribed 1/4S31 BT 12" D.B.H. White Fir, N.59°E., 25.7', Scribed 1/4 S31BT Both B.Ts. have brass washer marked RPLS 1910 between B&T, Red painted bands, B.T. tags, attention signs, steel fence post East on Section line and West of corner with attention, monument and boundary signs attached to proper posts.

Office of Surveyor Oregon County of Umatilla State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 30th day of September, 1982 David Krumbein by Betty Shatto (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 9-82 Rec'd by BRS No. 82-111-R

☆ GPO-798-276