

Index
File No. G-9
T 3N R. 38E
Merid. WILLAMETTE

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Tract or
Survey No. _____
Cor. No. _____

R.D. WALLA WALLA County UMATILLA
N.F. UMATILLA State OREGON

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND



NONE - CORNER IS IN A SMALL DRAW & STONE PROBABLY WAS WASHED AWAY IN HIGH WATER.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE WERE SET.
RECOVERED 1901 & 1899 CORNERS AS FOLLOWS:
(BOTH WERE SUPERCEDED IN 1903)

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature _____

1901 CORNER: ORIG. 28" TAMARACK IS A 30" LARCH SNAG WITH HEALED BLAZE, BEARS N81°W,

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
71,28 FEET. ORIG. 30" TAMARACK IS DOWN, HAS DOUBLE UNHEALED BLAZES WITH ALL SCRIBING CHOPPED OUT. ROOT HOLE BEARS N36°E, 42.9 FT. FROM THIS CORNER THE 1903 CORNER BEARS (RECORD) S20°W, 297.66 FEET. 1899 CORNER: ORIG. 24" TAMARACK IS NOW A 30" LARCH SNAG, WITH (CONTINUED ON BACK)

Signature W. Dennis Layford Title _____ Division PLS 1636 Headquarters _____ Date SEPT 25, 1997 FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

I PUT BT SIGNS ON THE TWO STANDING LARCH
SNAG BEARING TREES.

Work Done By _____ Title _____ Date _____ State Registration No. or Agency _____

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

1899 CORNER EVIDENCE, CONTINUED;
A HEALED BLAZE. BEARS $59^{\circ}30'W$, 38.94 FEET, ORIG. 22"
TAMARACK IS DOWN & BADLY DECAYED. NO MARKS REMAIN.
BROKEN STUMP BEARS $578^{\circ}E$, 44.22 FEET. FROM THIS CORNER
THE 1901 CORNER BEARS (RECORD) $541^{\circ}E$, 124.74 FEET.

Index File No. T. R. M. Tract or Surv. No. Cor.

G-9 T3N R3BE WILL