

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No. **N.F. UMATILLA** Cor.
No. **AP-664**


T. 3 N. R. 38 E.

R.D. WALLA-WALLA County UMATILLA

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
From the junction of F.S. roads 3100 and 3100-360, travel northwesterly on road 3100-360 approx. 2.4 miles to the end of the road. From this point go west approx. 150 feet to the Buck creek Rim trail and proceed northerly on the trail approx. 800 feet. At this point descend to the west approx. 200 feet to the corner which is located in a natural opening at an elevation of 5000 feet.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,620,731.77'
Y: 756,207.68'
Datum: NAD 1927

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set on the 5000 foot contour a 5/8" by 24" rebar, with a 3 1/4" aluminum cap, flush with ground, stamped "NFU WILDERNESS AP-664 RLS 2308 1996".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

25" Douglas Fir, S. 6° E., 74.5 feet, mkd. "WB/664" "BT".

17" Douglas Fir, N. 85° W., 85.1 feet, mkd. "WB/664" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T. **3 N.**

R. **38 E.**

M. **Willamette**

Tract or Survey No.

N.F. Umatilla Wild.

Cor. **AP-664**