

USDA-FOREST SERVICE

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No.

**N.F. Umatilla
Wilderness**


Cor.
No. **AP-734**

T. 3 N. R. 38 E.
Merid. Willamette

R.D. Walla-Walla
N.F. Umatilla

County Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES; ALSO HOW TO REACH CORNER

From the junction of F.S. roads 3100-320 and 3100-330 travel northwesterly on road 3100-330 approx. 2.5 miles to an earth barricade. From this point walk down the road approx. 450 feet to the center of a switchback. The corner is located on the crest of the ridge 100 feet northerly of the road and westerly of a trail.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,614,636.56'
Y: 756,519.51'
Datum: NAD 1927

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
10/1996

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set on the crest of a ridge 100 feet northerly of and perpendicular to abandoned road 3100-287, a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, stamped "NFU WILDERNESS AP-734 RLS 2308 1996".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

15" Englemann Spruce, N. 53° E., 30.9 feet, scribed "WB/734" "BT".

21" Western Larch, N. 58 1/2° W., 23.6 feet, scribed "WB/734" "BT".

Shamrock Spring, N. 73 3/4° W., 160.7 feet.

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich Title Land Surveyor Date 10/1996 State Registration No. or Agency _____

Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T. **3 N.**

R. **38 E.**

M. **Willamette**

Tract or Survey No.

N.F. Umatilla Wild.

Cor.

AP-734