

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 23
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 8, 1879, under GLO contract No. 332, as follows:

Set a basalt stone, 20" x 12" x 4", on west side of spur for 1/4 section corner.

T3S R30E
1/4 S1
S12
PLS 1636
2003

Original corner evidence recovered:

Found the original corner stone set loosely in the ground and tipped to the east. The corner stone is 20" x 16" x 4" and is plainly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original position of this corner:

At the point occupied by the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 14" into the ground to bed rock. I partially bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N50° 30' E, 50.9 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S29° 30' E, 85.7 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SW" attached at ground level, bears S33° 30' W, 61.8 feet.

A 5/8" x 18" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N50° W, 80.4 feet.

A newly constructed wire fence, projecting north and south, bears west, 6.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 26, 2003.

Magnetic declination set in compass: 17° E.

NAD '83 UTM Zone 11 position: 5021305N 340775E (plus or minus two meters).



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY

Umatilla County Surveyor

Date 9-03

Rec'd By KK

No. 03-260-R