

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 21
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 4, 1879, under GLO contract No. 332, as follows:

Set a basalt stone, 20" x 8" x 5", on southwest face of hill for corner to sections 11, 12, 13 and 14. Also set a post in a mound of stone.

T3S R30 1/2E
S11|S12
S14|S13
PLS 1636
2003

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 18" x 9" x 6" and is plainly marked with two notches on one edge. The post of record is gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the iron pipe is marked as shown in the diagram above. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 12", attached at ground level, bears N45° 30' E, 70.7 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 13", attached at ground level, bears S60° 30' E, 72.4 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 14", attached at ground level, bears S60° W, 61.2 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 11", attached at ground level, bears N38° 30' W, 90.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 23, 2003.

Magnetic declination set in compass: 17° E.

NAD '83 UTM Zone 11 position: 5019663N 341750 E (plus or minus two meters).



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY

Umatilla County Surveyor

Date 9-03

Rec'd By KR

No. 03-262-R