

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 11
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 4, 1864, under GLO contract No. 106, as follows:

Set stone 18" x 12" x 6" for 1/4 section corner.



Corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 16" x 12" x 8" and is plainly marked "1/4" on the south face.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe 27" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 36" iron rod set 31" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N52°30'E, 124.9 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S31°E, 115.4 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S46°W, 117.2 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N34°W, 116.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 1, 1998. Magnetic declination: 18°E.



Renews June 30, 1999

Recorded and the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

98-68-R