

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 14, 1879, under GLO contract No. 319, as follows:

T3S R31E
1/4
S5|S4
PLS 1636
1998

Set a basalt stone 24" x 14" x 9" on west face of hill for 1/4 section corner.

Corner evidence recovered:

The original corner stone is solidly set in a mound of stones. The stone is 26" x 14" x 8" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 26" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N50°30'E, 74.3 feet.
A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S29°E, 186.5 feet.
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S37°30'W, 119.1 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N44°W, 113.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 1, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY

Umatilla County Surveyor

Date 4-98

Rec'd By KR

No. 98-69-R