

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 9
DIAGRAM

History of original corner monumentation:

The original corner was established by George S. Pershin on May 14, 1879, under GLO contract No. 319, as follows:

Set stone 16" x 10" x 10" in mound of stone on level for corner to sections 4, 5, 8 & 9.

T3S R31E
S5|S4
S8|S9
PLS 1636
1998

Corner evidence recovered:

The original corner stone is solidly set in a mound of stones. The stone is 17" x 12" x 10" and is marked with four notches on the east edge and one notch on the north edge. The corner is located about 20 feet northeast of a farm road which courses northwest and southeast.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 27" into the ground. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N38°E, 122.7 feet.
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S34°E, 104.6 feet.
A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S75°W, 140.3 feet. This reference is southwest of the farm road mentioned above.
A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N31°W, 148.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 29, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1976
DENNIS L. GAYLORD
1636

Renews 6/30/1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 4-98
Rec'd By JK
No. 98-70-R