


History of original corner establishment:

This corner was originally established by George S. Pershin under Contract No. 304 on November 6, 1878. It was made a corner of minimum control in 1882 by the township subdivision survey in T.3 S., R.32 E., also by George S. Pershin. The 1878 record is:



Set stone 18" x 10" x 6" at foot of ridge on east side of creek for corner to sections 12, 13, 7 and 18, from which;

- A 20" Fir bears N71°E, 52 links (34.32 feet)
- A 7" Fir bears S48°E, 69 links (45.54 feet)
- A 30" Tamarack bears S45°W, 101 links (66.66 feet)
- A 10" Fir bears N40°W, 86 links (56.76 feet)

Description of corner evidence found:

Found the original corner stone solidly set in a mound of stones and marked with three notches on the north edge. The stone is 20" x 11" x 7" and is referenced by the following bearing tree remnants:

A 30" sawn Western Larch stump with scribes, "BT", visible bears S43°W, 66.5 feet.

A decayed and broken Fir snag of indeterminate size with full scribes visible bears N35°W, 56.8 feet.

A decayed Fir stump of indeterminate size, no marks remaining, bears N70°E, 33.6 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" by 30" galvanized iron pipe, with a 2 1/2" brass cap attached, 8" into the ground to bed rock. I placed the corner stone horizontally at the base of the pipe and built a mound of stones around the pipe to the cap. The cap is marked as shown in the diagram. From which new bearing trees:

A 6" Douglas Fir bears S26°W, 4.0 feet scribed "T3S R31E S13 BT" on a single blaze.

A 17" Spruce bears N74°W, 38.9 feet scribed "T3S R31E S12 BT" on a single blaze.

Both new bearing trees have a 3/4 inch brass washer, marked "PLS 1636", nailed flush to the lower part of the blaze and a "Umatilla County Bearing Object" sign nailed above the blaze.

I set a 5' steel fence post, with a "Umatilla County Witness Post" sign attached, 2 feet west of the corner.

I hereby certify the above corner position was perpetuated as hereon described on July 2, 1987. De: 20°E Witness: Steven J. Scritchfield



Office of County Surveyor..... County of Umatilla
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 4 day of August, 1987
 David H. Klein by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 8-87
 No. 87-46-R