


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-25

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that a 17" x 12" x 4" stone was set near summit from which:



- A 8" dia Fir bears N54°E 39 lk dist.
- A 7" dia Pine bears S21°E 64 lk dist.
- A 24" dia Fir bears S24°W 38 lk dist.
- A 12" dia Pine bears N38°W 53 lk dist.

No record of restoration appears in County Records.

Description of corner evidence found:

A 22" dia Pine Stump bears N38°W 34.98 ft dist tagged S38°E 34.98 ft dist with visible scribing "T3S R31E" (original BT)

Description of monument and accessories I established to perpetuate the original location of this corner:

By measuring record bearing and distance from found original BT stump I re-established the corner position I set:

A 2 1/2" brass cap on 2 1/2" x 30" l. pipe 20" in ground with mound of stone from which:

A 17" dia R Fir bears N 20 1/2°W 27.1 ft dist marked: T3S R31E/S13 BT.


A 13" dia P. Pine bears S87°W 37.3 ft dist marked: T3S R31E S24 BT.

Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54- 3 and 4 signs. Each new BT has lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 4, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of..... Umatilla

State of..... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

.....*David H. Krumbein* by *Betty L. Skatte*.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-137-B

☆ GPO-798-276